The ArchiTech Design

ALL INTERIOR & EXTERIOR SOLUTION'S

Architects | Home Construction | Interior Designing | Modular Kitchen

Gorakhpur | Lucknow | Delhi-NCR

GSTIN: 09BXNPA4874M1ZT
Website- https://www.thearchitechdesign.com
Call us on :- 8587810424 , 9336544103

The Architech Design Construction Packages

S. No.	Details	Budget Package INR 1699/- per sq.ft.	Standard Package INR 1899/- per sq.ft.	Classic Package INR 2099/- per sq.ft.
1	**Drawings & Details**	Floor Plan Furniture Layout 3D Exterior Elevation	Floor Plan Furniture Layout 3D Exterior Elevation Structural Drawing (Footing, Beams, Columns, Slabs) Working Drawings	Floor Plan Furniture Layout 3D Exterior Elevation Structural Drawing (Footing, Beams, Columns, Slabs) Working Drawings Plumbing & Drainage Drawings Electrical Drawings
2	**Foundation Work**	Excavation- Upto 5 feet below Ground Level PCC- As per Requirement Foundation - As per Structural Drawing Plinth Beam- As Per Drawing	Excavation- Upto 5 feet below Ground Level PCC- As per Structural Drawings Foundation- As per Structural Drawings Plinth Beam- As Per Drawing (All Designs at par with IS 456:2000)	Excavation- Upto 5 feet below Ground Level PCC- As per Structural Drawings Foundation- As per Structural Drawings Plinth Beam- As Per Drawing (All Designs at par with IS 456:2000)
3	**Structural Details**	Aggregates-10mm,20mm,40mm (As required) Cement- Prism/Birla Steel- Gallant RCC- M-20 (1:1.5:3) Brick Work- First class 9" Outer Walls (1:5) 4.5" Inner Walls (1:4) Plaster - (1:4) 1 Coat Ceiling Height- 10 feet clear height	Aggregates-10mm,20mm,40mm (As required) Cement- Ultratech Steel- Kamdhenu NXT RCC- M-20 (1:1.5:3) Brick Work- First class 9" Outer Walls (1:5) 4.5" Inner Walls (1:4) Plaster - (1:4) 1 Coat Ceiling Height- 10.5 feet clear height	Aggregates-10mm,20mm,40mm (As required) Cement- ACC Suraksha Steel- Tata Steel RCC- M-20 (1:1.5:3) Brick Work- First class 9" Outer Walls (1:5) 4.5" Inner Walls (1:4) Plaster - (1:4) 1 Coat Ceiling Height- 11 feet clear height
4	**Bathrooms**	Wall Tiles- 7 feet height ceramic tiles upto Rs. 40 per sq.ft. Floor Tiles- Vitrified tiles upto Rs. 40 Per sqft. Sanitary Fittings- EWC upto Rs. 4000/- (Cera/Parryware) CP Fittings-Wall Mixer, Shower, Towel Rail, Soap Dish, Health Faucet Upto Rs. 10,000/- (Cera)	Wall Tiles- 7 feet height ceramic tiles upto Rs. 50 per sq.ft. (Kajaria/Johnson) Floor Tiles- Vitrified double charged tiles upto Rs. 55 Per sqft.(Kajaria/Johnson) Sanitary Fittings- EWC upto Rs. 8000/-+ Wash Basin Upto Rs 2000/-INR (Hindware) CP Fittings- Pillar Cock, Wall Mixer, Shower, Towel Rail, Soap Dish, Health Faucet Upto Rs. 15,000/- (Hindware/Jaquar) Water Proofing- Using Dr. Fixit	Wall Tiles- 7 feet height ceramic tiles upto Rs. 65 per sq.ft. (Kajaria/Johnson) Floor Tiles- Vitrified double charged/ Glossy/Matt/Full body type tiles upto Rs. 70 Per sqft.(Kajaria/Johnson) Sanitary Fittings- EWC upto Rs. 12000/-+ Wash Basin Upto Rs 3000/-INR (Hindware) CP Fittings- Pillar Cock, Wall Mixer, Direct water Bib cock Shower, Hand Shower, Towel Rail, Soap Dish, Health Faucet Upto Rs. 20,000/- (Jaquar) Water Proofing- Using Dr. Fixit
5	**Kitchen**	Wall Tiles- Upto 2 feet above kitchen slab (upto Rs. 40 per sq.ft.) Floor Tiles- Vitrified double Charged (upto Rs.40 per sq.ft.) Kitchen Slab- Granite Upto INR 150 per sq.ft. Sink-Stainless Steel with faucet upto Rs.3000/-	Wall Tiles- Upto 2 feet above kitchen slab (upto Rs. 50 per sq.ft.) Kajaria/Johnson Floor Tiles- Vitrified double Charged (upto Rs.55 per sq.ft.) (Kajaria/Johnson) Kitchen Slab- Granite Upto INR 170 per sq.ft. Sink-Stainless Steel with faucet (Jaquar /Hindware/Parryware) Upto Rs. 4500	Wall Tiles- Upto 2 feet above kitchen slab (upto Rs. 65 per sq.ft.) Kajaria/Johnson Floor Tiles- Vitrified (double Charged/ Glossy/Matt/Full body tiles) (upto Rs.70 per sq.ft.) (Kajaria/Johnson) Kitchen Slab- Granite Upto INR 200 per sq.ft. Sink-Stainless Steel Double Bowl (Carysil) with faucet (Jaquar) Upto Rs. 8000/- Water Proofing- Using Dr. Fixit

6	**Doors & Windows**	Frame/Chaukhat- Iron Pipe Main Door- Flush doors with Laminates (7'*x3') upto Rs. 9000/- incluiding all fittings Internal Doors- Flush Doors (7' * 3') with Laminates Upto INR 5500/-incluiding fittings Windows- UPVC Window 2 track with 5mm Glass Shutter Upto INR 350 per sq.ft Window Grill- Basic MS Pipe @ 1.2kg per sq.ft	Frame/Chaukhat- Iron Pipe (For Main Door- 5" by 3" & Internal doors 4" by 2.5") Main Door- Teak (Sagwan Door Upto Rs. 15,000/-) (7' * 3'3") Incluiding all fittings Internal Doors- Flush Doors (7' * 3') with Laminates Upto INR 7000/-incluiding fittings Windows- UPVC/Plywood Shutter Window with 5mm Glass Shutter Upto INR 450 per sq.ft Window Grill- Basic MS Grill @ 1.6kg per sq.ft	Frame/Chaukhat- Malaysian Sakhu Frame (For Main Door- 5" by 3" & Internal doors 4" by 2.5") Main Door- Teak (Sagwan Door Upto Rs. 20,000/-) (7' * 3'3") Incluiding all fittings Internal Doors- Flush Doors (7' * 3') with Laminates Upto INR 9000/- incluiding fittings Windows- UPVC slider 3 track Window Upto INR 550 per sq.ft Window Grill- Basic MS Grill @ 2kg per sq.ft
7	**Painting**	Internal- 2 Coat Putty + 1 Coat Primer + 2 Coat Paint (JK Putty, Berger & Rangoli) External - Berger, Nerolac	Internal- 2 Coat Putty + 1 Coat Primer + 2 Coat Paint (JK Putty & Asian Tractor Shyne Emulsion) External - Asian Ace Exterior Emulsion	Internal- 2 Coat Putty + 1 Coat Primer + 2 Coat Paint (JK Putty & Asian Royal Emulsion) External - Asian Apex Ultima
8	**Flooring**	Living Room & BedRooms- 2'*2' Vitrified Tiles Upto Rs. 40 per sq.ft. (Kajaria/Johnson)	Living Room & BedRooms- 2'*2' Vitrified Tiles Upto Rs. 55 per sq.ft. (Kajaria/Johnson) Staircase- Marble/Granite upto Rs. 80 per sq.ft Parking Tiles- Anti Skid upto Rs. 35 per sq.ft.	Living Room & BedRooms- 2'*2' or 4'*2' Vitrifie Tiles (Double charged/Matt/Glossy/Full body Tiles) Upto Rs. 70 per sq.ft. (Kajaria/ Johnson) Staircase- Marble/Granite upto Rs. 90 per sq.ft Parking Tiles- Anti Skid upto Rs. 40 per sq.ft.
9	**Plumbing**	Internal Plumbing- CPVC Pipe and CPVC Fittings (Prince) Sewer lines- Internal, External and Vertical all CPVC pipes and fittings (Prince) Water Supply- From Boring/Pump to overhead tank in CPVC pipes and fittings Overhead Tanks- 500L (Prince) Double Layered	Internal Plumbing- CPVC Pipe and CPVC Fittings (Ashirvad) Sewer lines- Internal, External and Vertical all CPVC pipes and fittings (Ashirvad) Water Supply- From Boring/Pump to overhead tank in CPVC pipes and fittings Overhead Tanks- 1000L (Prince) Double or Triple Layered	Internal Plumbing- CPVC Pipe and CPVC Fittings (Supreme) Sewer lines- Internal, External and Vertical all CPVC pipes and fittings (Supreme) Water Supply- From Boring/Pump to overhead tank in CPVC pipes and fittings Overhead Tanks- 2000L (Ashirvad)Double or Triple Layered
10	**Electrical**	Copper Wires- KEI or Kent Switches & Sockets- Anchor Penta	Copper Wires- Polycab Switches & Sockets- Modular switches (Anchor Rider)	Copper Wires- Havells Switches & Sockets- Modular switches (Anchor Roma)
11	**Miscellaneous**	Staircase Grill- MS Pipe Railing with Paint	Staircase Grill- MS Railing with Enamel Paint Balcony- MS Steel with Enamel Paint	Staircase Grill- MS Railing Designer Railing Balcony- MS Steel Designer Railing

General Notes-

1) The prices quoted above are tentative in nature which may vary slightly depending on actual site conditions & drawing.
2) Boring Work will be charged separately as per depth .
3) External elevation Design will be charged separately .
4) Scope of work only under the slab area will be considered in contract, any other work will be charged extra.
5) Foundation work if in case required beyond a depth of 5 feet will be charged separately.
6) Plinth level earth work, soil filling will be done by using the soil at site only and in case required extra will be paid additionally by client.
7) Waterproofing on terrace will be charged extra.
8) Electricity, water connection and any government charges pertaining to it are not covered.
9) Electricity, water supply and labour hutment will be provided by client free of cost.
10) Boundary wall, Parapet wall, Mumty work, Brick Coba, Main Iron Gate, Lift Room, Retaining Walls, outside. Plumbing and Landscaping is not included in the scope of work and will be charged extra.
11) Connection of internal sewer line to main government sewer line is not included.
12) Septic tank and Sokhta in case needed will be charged separately.
13) The packages quoted above are for Duplex home construction.
14) Plan approvals from Local Development Authority and govt. fees and all charges pertaining to it is under client's scope.
15) Prices are valid for 15 Days Only.

Payment Terms-

1) Once the agreement is finalised Mobilisation Advance 15% of the entire project cost has to be paid by client which will be adjusted in equal bifurcation at completion of each slab level.

2) Excavation & Footings- 25%
(Excavation -25%, Reinforcement- 50%, Casting- 25%)

3) Super Structure- 45%
(Column- 30%, Slab- 30%, Brickwork-20%, Plaster- 20%)

4) Finishing Work- 30%
(Door & Windows- 25%, Electrical & Plumbing- 25%, Flooring-25%, Putty & Paint- 25%)